Project Name: Coppei Creek Project Area 07

Construction Cost Estimate

Preliminary 30% Design

Class 3 Estimate (-20% to +30%)

Item Description	Quantity	Unit	Un	it Cost	Cost	E	xtended Cost	Assumptions
General						\$	108,483	
Mobilization and Demobilization	1	LS	\$	41,008	\$ 41,008			8% of total (excluding tax and contingency)
SPCC Plan Development and Implementation	1	LS	\$	5,000	\$ 5,000			
ESC Plan Development and Implementation	1	LS						
Construction and Driveway Entrance	5	EA	\$	3,000	\$ 15,000			
Straw Wattles	600	LF	\$	4.50	\$ 2,700			
Clearing	0.5	AC	\$	10,000	\$ 4,562			
Cofferdams, Pumping, and Dewatering	1	LS	\$	10,000	\$ 10,000			
Surveying	1	LS	\$	5,000	\$ 5,000			
Temporary Stabilized Access Route	2,027	SY	\$	8	\$ 16,213			Wood chips or gravel; 20% of 7,600 LF
Temporary Log Stream Crossing	3	EA	\$	3,000	\$ 9,000			
Site Work						\$	404,192	
Excavation	1,850	CY						
Channel Excavation	885	CY	\$	6	\$ 5,310			
Levee Excavation	965	CY	\$	6	\$ 5,790			
Off-Site Haul	1,850	CY	\$	16	\$ 29,600			
Constructed Riffle Material	50	CY	\$	75	\$ 3,750			Includes install
LWD Acquisition and Delivery	1	LS	\$	269,542	\$ 269,542			
HS-1 - Three Log Structure	14	EA	\$	550	\$ 7,700			Structure install
HS-2 - Single Log Structure	200	EA	\$	200	\$ 40,000			Structure install
HS-3 - Whole Tree Structure	53	EA	\$	300	\$ 15,900			Structure install
HS-4 - Bleeder Jam Structure	11	EA	\$	800	\$ 8,800			Structure install
HS-5 - Small Apex Jam Structure	4	EA	\$	700	\$ 2,800			Structure install
Willow Baffle	600	LF	\$	25	\$ 15,000			Structure install
Soil Decompaction, Planting, and Seeding						\$	40,927	
Riparian Seeding and Planting	4.55	AC	\$	9,000	\$ 40,927			
Subtotal						\$	553,602	
Markups								
Estimating Contingency	10.0%		\$	55,360				
Total						\$	608,962	
Estimated Construction Cost (Base)						\$	609,000	
Low Side (-20%)						\$	488,000	
High Side (+30%)							792,000	
Notes								

<u>Notes</u>

^{1.} All estimated item costs include full compensation for all materials, labor, equipment, and all appurtenances unless noted or itemized separately.

^{2.} Class 3 estimates are generally prepared to form the basis for budget authorization, appropriation, and/or funding. As such, they typically form the initial control estimate against which all actual costs and resources will be monitored. Typically, engineering is from 10 to 40 percent complete. Class 3 estimates usually involve more deterministic estimating methods and usually involve high degree of unit cost line items, although these may be at an assembly level of detail rather than individual components.